

Report 1: Funded Schemes

Funded Schemes 2018-19

Total Value of Schemes	£260,500
------------------------	----------

Ref	Scheme name	Description	Parish	Scheme Category	Scheme stage	Cost Code	Allocated Budget	Comments	Est completion
1	Aetheric Road Roundabout	1. That the give way signing and lining is removed from the eastern arm of Panfield Lane and replaced with a mini roundabout sign and suitable lining 2. That the mini roundabout sign and roundabout give way markings are removed and replaced with a new yellow backed give way sign and new give way markings on Panfield Lane west 3. A cycle warning sign is erected on the northbound approach to the roundabout on Aetheric Road 4. Refresh all lining within 100m of the roundabout	Unparished	Safer Roads	Total scheme	LBRA181004	£17,000	Awaiting UKPN.	Q2
2	The Street B1137 j/w A12	1. Lay a new 50mph roundel carriageway marking at the 50mph Terminals 2. Install a VAS "50" "SLOW DOWN" if it meets the criteria 3. Provide a new bolt down traffic island complete with bollards and high mounted posts and SLOW road marking, to create a narrowing effect for eastbound motorists 4. Replace damaged signpost and remount existing yellow backed give way sign at the right turn lane	Hatfield Peverel	Safer Roads	Total scheme	LBRA181005	£29,500	Awaiting installation of the VAS face.	Q2
3	Millennium Way, Braintree	Undertake a study to investigate capacity at the junction. If there is sufficient capacity provide a separate right turn phase for the signals complete with new signal head	Unparished	Safer Roads	Feasibility	LBRA181006	£10,000		
4	A131, Great Notley - Panners roundabout adj to Hungry Horse public house	Undertake a detailed design for a signalised crossing	Great Notley	Traffic Management	Design	LBRA152064	£27,500	Additional £8,500 will be needed to review the target cost and liaise with UKPN.	

Report 1: Funded Schemes

Funded Schemes 2018-19

Total Value of Schemes	£260,500
------------------------	-----------------

Ref	Scheme name	Description	Parish	Scheme Category	Scheme stage	Cost Code	Allocated Budget	Comments	Est completion
5	Clare Road, Belchamp Road, Tilbury Road – Tilbury Juxta Clare - TMI	<p>Clare Road - Install the bend warning signage from Belchamp Road and install a bend warning sign by the set of properties, both to have advisory 30mph sub plates</p> <p>Belchamp Road – upgrading chevron signs, adjacent to the public footpath. Where the carriageway is not 5.5 metres in width remove centre lines</p> <p>Tilbury road - Where the carriageway is not 5.5 metres in width remove centre lines</p>	Tilbury Juxta Clare	Traffic Management	Total scheme	LBRA162036	£18,000		
6	A1017 Yeldham Road, north of Nunnery Street - TMI	Install a 40mph Speed Indicator Device and additional repeater signs	Sible Hedingham	Traffic Management	Total scheme	LBRA162052	£13,000		
7	Inworth Road, Feering	To carry on with the legal process for the implementation of the remaining section of footway	Feering	Traffic Management	Feasibility	LBRA162021	£2,000	Land cannot progress any further as residents do not want to give up their land.	
8	Cressing Road, Witham outside Templars School	Undertake a feasibility study to determine if a zebra crossing can be installed outside Templars Academy	Witham	Walking	Feasibility	LBRA173005	£8,000		
9	Halstead High Street - Raised kerbs	Undertake a feasibility study to determine if raised kerbs could be installed at this location. May also have to look into potential drainage issues	Halstead	Passenger Transport	Feasibility	LBRA175001	£4,000		
10	Chipping Hill Bridge, Chipping Hill j/w Powers Hall End, Witham	Implementation of measures from the detailed design. Cost is an estimate as we are still awaiting a quote from UKPN	Witham	Traffic Management	Total Scheme	LBRA162004	£39,000		
11	Hedingham Road, Bulmer - One way	Request for a design to determine if a build out could be looked into to prevent vehicles travelling the incorrect way along a one way system	Bulmer	Traffic Management	Feasibility	LBRA162076	£4,000		

Report 1: Funded Schemes

Funded Schemes 2018-19

Total Value of Schemes	£260,500
------------------------	-----------------

Ref	Scheme name	Description	Parish	Scheme Category	Scheme stage	Cost Code	Allocated Budget	Comments	Est completion
12	A1124 Colchester Road and roundabout j/w Fenn Road	Request to look into measures to improve the visibility of the mini roundabout	Halstead	Traffic Management	Feasibility	LBRA162065	£5,500		
13	Yeldham Road, Sible Hedingham	Undertake a feasibility to determine if the layby could be extended or if the layout could be changed	Sible Hedingham	Traffic Management	Feasibility	LBRA182002	£6,500		
14	Syers Field, Blackmore End, Wethersfield	Undertake a feasibility to determine if the layby could be extended	Wethersfield	Traffic Management	Feasibility	LBRA182007	£5,500		
15	B1256 Rayne Road, Braintree - Zebra crossing	Undertake a feasibility study to determine if a zebra crossing can be installed close to Lidl	Unparished	Walking	Feasibility	LBRA173008	£6,500		
16	Halstead Road, Gosfield - Bus shelter	Install a bus shelter	Gosfield	Passenger Transport	Total scheme	LBRA185001	£12,000		
17	Rowley Hill opposite Crunch Croft, Sturmer - Bus shelter	Install a bus shelter	Sturmer	Passenger Transport	Total scheme	LBRA185002	£12,000		
18	The Street, Hatfield Peverel - Bus shelter	Install a bus shelter	Hatfield Peverel	Passenger Transport	Total scheme	LBRA185003	£12,000		
19	Ashes Road, Cressing	Install advanced bend warning signage and farm traffic warning signs	Cressing	Traffic Management	Total scheme	LBRA172027	£4,000		
20	Spa Road, Witham	Request to reduce the size of an old road sign or relocate it as it is causing visibility issues for people waiting at the bus stop	Witham	Traffic Management	Total scheme	LBRA172028	£4,000		
21	Ridgewell Road, Great Yeldham - Directional signage	Request to install directional signage to the cemetery and recreation ground	Great Yeldham	Traffic Management	Total scheme	LBRA162071	£8,000	Stats which were not recorded were found on site so sign could not be installed. A new location has been found however a cantilever bracket was needed.	Q2
22	Valentine Way, Silver End - Trees	Request to plant trees in Valentine Way, Silver End	Silver End	Traffic Management	Total scheme	LBRA182020	£4,500		
23	Western Road, Silver End	Request to install dropped kerbs	Silver End	Walking	Total scheme	LBRA183001	£8,000		

Report 1: Funded Schemes

Schemes Funded 2019-20

Total Value of Schemes	£345,500
------------------------	-----------------

Ref	Scheme name	Description	Parish	Scheme Category	Scheme stage	Cost Code	Allocated Budget	Comments	Est completion
1	Braxted Road,	Verge marker posts and signing	Rivenhall	Safer Roads	Total scheme	LBRA191001	£6,500		Q2
2	A131 / London Road RAB, Great Notley	Signing and lining	Great Notley	Safer Roads	Total scheme	LBRA191002	£46,000		Q3
3	A131 Halstead Road 385m South of Petersfield Lane	Verge marker posts and signing	Unparished	Safer Roads	Total scheme	LBRA191003	£6,000		Q2
4	Millennium Way Braintree	Undertake a design to provide a separate right turn phase	Unparished	Safer Roads	Design	LBRA181006	£8,000		Q3
5	B1018 Witham Rd Temple Lane	Design to see if there are any possible improvements to the Bennet island or if the island could possibly be removed	Cressing	Safer Roads	Design	LBRA181007	£21,000		Q3
6	Boars Tye Road, Silver End - Footway	Footway	Silver End	Walking	Design	LBRA163006	£7,000		Q3
7	Finchfield Road, Steeple Bumpstead - layby	Layby	Steeple Bumpstead	Traffic Management	Design	LBRA162020	£6,500		Q3
8	Colchester Road close to Nether Court - Dropped kerbs	Dropped kerbs	Halstead	Traffic Management	Implementation	LBRA162072	£10,000		Q1
9	Colne Road to the Colchester bound carriageway of the A120- Junction	Dedicated left hand lane from Colne Road to the A120	Coggeshall	Traffic Management	Feasibility Only	LBRA172010	£6,500		Q4
10	Maldon Road j/w Blue Mills Hill - Signal timings	Change signal timings	Witham	Traffic Management	Total scheme	LBRA172015	£10,000	The current timings are 7:15-9:00am and 4:00-7:00pm the suggested alternative times would be 6:00-9:30am and 3:30-7pm.	Q4
11	Mitchells Avenue, Halstead - Signing	Land negotiations for potential signs	Halstead	Traffic Management	Feasibility	LBRA172016	£2,000		Q4

Report 1: Funded Schemes

Schemes Funded 2019-20

Total Value of Schemes	£345,500
------------------------	-----------------

Ref	Scheme name	Description	Parish	Scheme Category	Scheme stage	Cost Code	Allocated Budget	Comments	Est completion
12	Old Challis Rise – Salt Bin	Land negotiations for potential salt bin	Rayne	Traffic Management	Feasibility	LBRA172036	£2,000		Q3
13	B1018 Braintree Road, Cressing - Footway improvements	Footway improvements	Cressing	Walking	Total Scheme	LBRA193001	£15,000		Q3
14	Audley End, Gestingthorpe - VAS	VAS	Gestingthorpe	Traffic Management	Total scheme	LBRA182023	£10,000		Q2
15	Vicarage Road, Finchingfield - 20's Plenty	20's Plenty	Finchingfield	Traffic Management	Total scheme	LBRA182024	£5,000		Q2
16	Valentine Way, Silver End - Grasscrete phase 2	Grasscrete	Silver End	Traffic Management	Total scheme	LBRA182028	£56,000		Q3
17	A1124 Colchester Road and roundabout j/w Fenn Road - Roundabout improvements	Improvements to the approach of the mini roundabout	Halstead	Traffic Management	Total scheme	LBRA162065	£36,000		Q3
18	Heddingham Road, Bulmer- Junction realignment	Realignment of the junction to discourage illegal manoeuvres along one way	Bulmer Parish Council	Traffic Management	Total scheme	LBRA162076	£13,000		Q3
19	Colneford Hill/Colne Park Road, White Colne - Kerbing works	Land negotiations and kerbing design	White Colne	Traffic Management	Design	LBRA142020	£19,500		Q4
20	Hill Lane j/w the A1017, Sturmer - Footway improvements	Improvements to current footway	Sturmer	Walking	Design	LBRA173003	£5,500		Q4
21	Cressing Road, Witham outside Templars School - Zebra crossing	Zebra crossing	Witham	Walking	Design	LBRA173005	£5,500		Q4

Report 1: Funded Schemes

Schemes Funded 2019-20

Total Value of Schemes	£345,500
------------------------	-----------------

Ref	Scheme name	Description	Parish	Scheme Category	Scheme stage	Cost Code	Allocated Budget	Comments	Est completion
22	Halstead High Street – Raised Kerbs	Raised kerbs	Halstead	Passenger Transport	Design	LBRA175001	£4,000		Q3
23	Kestrel Rise, Halstead – Salt Bin	Land negotiations	Halstead	Traffic Management	Total scheme	LBRA172041	£500	Additional £2,000 will be needed for land negotiations.	Q4
24	Direct Delivery Schemes		District Wide	All	Total scheme		£41,000		Q4
25	Braintree Post Construction Audits	Road safety audits post scheme installation	District Wide	Surveys	Surveys	RSA3LBRA	£3,000		Q4